



- Scope of Work:
1. Coordinate with Wythe County, Gatorade, and Norfolk Southern Railroad. Randall Fowler Gatorade 276-625-3965. Johnny Kincer Wythe County 276-223-4512, Josh Riddle Norfolk Southern [Joshua.Riddle@nscorp.com](mailto:Joshua.Riddle@nscorp.com)
  2. Remove marked Ties.
  3. Install new Ties
  4. Re-gage rails entire curve in the Limits of Construction.
  5. Remove corroded rail and replace. Regage rail to 56.5 inches.
  6. Repair/Replace Crossing Rubber as needed.

- Specifications:
1. Rail Road specification to be adhered to. Coordinate with Josh Riddle 276-698-6316.
  2. Rail Road Flagging may be required.
  3. Schedule downtime with Gatorade.

Gage entire curve to 56.5 inches inside rail to inside rail.  
Replace Marked Ties.



Wythe County Virginia  
340 South 6th Street  
Wytheville, VA 24382  
Phone 276-223-4500

RR TIE  
Replacement  
Site Plan  
Spur Line to  
Gatorade Plant

Date 6-14-21 Revised 7-3-25		
Not To Scale		
No.	Revision	Date